

BRUHAT BANGALORE MAHANAGAR PALIKE**Project Division, Yelahanka Zone****SCHEDULE - B****Improvements of roads and drains at Thirumenhalli Lake road and surrounding area in Ward No.05 (Jakkur)**

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. E Ramesh Anand	
				In figures	In words
1	2860.94	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1,KPWD SR 2018-19) 8km lead= 57+2.0x1.28x88 =77.48	Cum	226.04	Rupees Two Hundred Twenty Six And Paise Four Only
2	392.19	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18,KPWD SR 2018-19)	Cum	5693.00	Rupees Five Thousand Six Hundred Ninety Three Only
3	39.73	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. Specificatio (I No-28.8.2,P No-229,KPWD SR 2018-19)	MT	75943.33	Rupees Seventy Five Thousand Nine Hundred Forty Three And Paise Thirty Three Only
4	662.13	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm (I No-37.59.2,P No-271,KPWD SR 2018-19)	Cum	7423.71	Rupees Seven Thousand Four Hundred Twenty Three And Paise Seventy One Only
5	113.40	KSRB 5.2 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar, stone hammered dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 cement mortar 1:6 KBS 5.1.13 (I No-5.6,P No-25,KPWD SR 2018-19)	Cum	5115.35	Rupees Five Thousand One Hundred Fifteen And Paise Thirty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Quantity	Item Name	Unit	Approved Rates of Sri. E Ramesh Anand	
			In figures	In words
54.24	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. (P.No-13,I No-4.6,KPWD SR 2018-19)	Cum	6034.69	Rupees Six Thousand Thirty Four And Paise Sixty Nine Only
2667.00	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete. (P.No-27,I No-5.30,KPWD SR 2018-19)	Nos	454.10	Rupees Four Hundred Fifty Four And Paise Ten Only
420.00	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. (P.No-180,I No-24.1,KPWD SR 2018-19)	Sqm	89.04	Rupees Eighty Nine And Paise Four Only
1891.80	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc ,complete. (Data Rate)	Sqm	2453.85	Rupees Two Thousand Four Hundred Fifty Three And Paise Eighty Five Only
261.00	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc ,complete. As per Engineer incharge ,KPWD SR.2018-19	Sqm	5688.90	Rupees Five Thousand Six Hundred Eighty Eight And Paise Ninety Only
250.00	Supplying PVC ring tight pipes conformin to IS 4980 :2000 With latest amendments and conveying to work site rolling and lowering into trenches laying true line level and prefect linking at joints testing and commisssoning incuding loading and un loading at both destinations and cuts of pipes wherever neccessary including joints of PVC pipes and specificals (excluding cost of pipes)with jointing of approval type with all labour with all lead and lift incuding encasing the pipe alround to adepth of not less then 15cms with soft gravel or selected earth availble from the excavation etc..., completed and giving necessary hydraulic test to the required pressure as per IS (Contractor will make his own arrangement for procuring water for testing)(P. No.133 I No 1.4 BWSSB SR 2018-19) 63mm outer dia, 6kg/sqcm & class 5	Mtr	128.10	Rupees One Hundred Twenty Eight And Paise Ten Only

Contractor


Executive Engineer
Project Division
Yelahanka Zone


Quantity	Item Name	Unit	Approved Rates of Sri. E Ramesh Anand	
			In figures	In words
1381.35	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specification No.301 Loading and unloading with 8km lead= (I No-19.14,P No-143,KPWD SR 2018-19)	Cum	67.14	Rupees Sixty Seven And Paise Fourteen Only
4604.50	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occurring during rolling including cost of all labour, HOM complete as per specifications.(I No-19.64,P No-147,KPWD SR 2018-19)	Sqm	6.68	Rupees Six And Paise Sixty Eight Only
525.02	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications.(I No-20.5,P No-153,KPWD SR 2018-19)	Cum	2094.67	Rupees Two Thousand Ninety Four And Paise Sixty Seven Only
512.66	KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18,KPWD SR 2018-19)	Cum	2101.34	Rupees Two Thousand One Hundred One And Paise Thirty Four Only
2278.50	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6,KPWD SR 2018-19)Issue rate Dated -01-07-2020	Sqm	31.16	Rupees Thirty One And Paise Sixteen Only
2278.50	KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7,KPWD SR 2018-19)Issue rate Dated -01-07-2020	Sqm	13.36	Rupees Thirteen And Paise Thirty Six Only
113.93	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 505 of MORTH V revision using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen (P.No-160,I No-21.17.6,KPWD SR 2018-19) Issue rate Dated -01-07-2020	Cum	6728.09	Rupees Six Thousand Seven Hundred Twenty Eight And Paise Nine Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Sl. No.	Quantity	Item Name	Unit	Approved Rates of Sri. E Ramesh Anand	
				In figures	In words
19	91.14	Providing and laying bituminous concrete 40mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. – do – using 40-60 TPH capacity HMP with mechanical paver grading II (30-45mm) with 5.4 % of modified bituminus binder consisting of 4.97% of VG-30 bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic) (P.No-171,I No-21.78.12,KPWD SR 2018-19) Issue rate Dated -01-07-2020	Cum	7914.54	Rupees Seven Thousand Nine Hundred Fourteen And Paise Fifty Four Only
20	348.90	KSRRB M600-1.Providing and Constructing dry lean cement concrete mix CC 1:5:10 base with OPC 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @0.58cum over a prepared sub-base, coarse and fine aggregate conforming to IS: 383-2016,aggregate cement ratio not to exceed 15:1, Aggregate gradation after blending to be as per Table 600-1,optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications. do- with OPC at 150 kg/cum and coarse aggregate 0.86cum, fine aggregate 0.58cum using Concrete Batch mix Plant at 75 cum/hr capacity with fixed form paver. (P.No-174,I No-21.1.2,KPWD SR 2018-19)	Cum	4079.15	Rupees Four Thousand Seventy Nine And Paise Fifteen Only
21	348.90	Cement concrete pavement Construction of un-reinforced plain cement concrete pavement, Thickness as per design, over a prepared sub base with 53 grade cement or any other type as per clause 1501.2.2 M30 (Grade) coarse and fine aggregate conforming to IS: 383 maximum size of coarse aggregate not exceeding 25mm , mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weight batcher as per approved mix design laid in approved fixed of 125 micron thick polythene film, wedges steel plates including levelling the form work as per drawing) Spreading the concrete with shovels rammers compacted using needle screed and plate vibrator and finished in a continuous operation including provision of construction joints primer joint sealant curing of concrete slabs for 14 days and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead lifts loading & unloading charges cost and conveyance of all materials (P.No-176,I No-22.6.1,KPWD SR 2018-19)	Cum	5469.34	Rupees Five Thousand Four Hundred Sixty Nine And Paise Thirty Four Only


Contractor


Executive Engineer
Project Division
Yelahanka Zone

Sl. No.	Quantity	Item Name	Unit	Approved Rates of Sri. E Ramesh Anand	
				In figures	In words
22	74.60	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15,KPWD SR 2018-19)	Sqm	454.00	Rupees Four Hundred Fifty Four Only
23		GST @ 12%(For SR 2018-19 Items Only)			

[Handwritten Signature]

[Handwritten Signature]
Contractor

[Handwritten Signature]
Executive Engineer
Project Division
Yelahanka Zone